BRUHAT BENGALURU MAHANAGARA PALIKE

TENDER DOCUMENT – KW4

(WORKS COSTING MORE THAN Rs. 100 LAKHS)

Name of Work: - Improvements to roads, drains and other developmental works at Akshaya, Tirumala Nagar, Attur layout, Santhosh nagara, Muneshwara layout, Sri Sai layout, B sector and surrounding areas in ward No 03 & 04 of Yelahanka Division under Amruth Nagarothan Grants. (PACKAGE No-03)

Estimate Cost: 2135.00 Lakhs

—

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

BRUHAT BENGALURU MAHANAGARA PALIKE

No: BBMP/EE/YNK.D/E-PMT/06/2022-23

Office of the Executive Engineer
Yelahanka division, Bangalore – 560064.
Dated: **24-06-2022**

INVITATION FOR TENDER (IFT)
(Short term- Tender Notification)
(Two Cover System)
(Through **GOK e–Procurement Portal** only)

1. The Executive Engineer Yelahanka Division invites tenders on behalf of the commissioner, BBMP, Bengaluru from eligible Tenderers for the construction of works detailed in the table below. The tenderers may submit tenders for works given in the table through e-procurement portal of the Government of Karnataka (viz https://eproc.karnataka.gov.in).The Tenderers are advised to note the minimum qualification criteria specified in Clause 3 of the Instructions to Tenderers to qualify for award of the contract **as per standard tender document KW-4**
2. Tenders must be accompanied by Earnest Money Deposit specified for the work in the table below. Earnest money deposit will have to be in any one of the forms as specified in the Tender document (Minimum of Rs.1,00,000/- through e-payment under of the following i.e., online/RTGS /NEFT /OTC and the balance by bank guarantee issued by Nationalized / Scheduled Bank and shall have to be valid for 180 days beyond the validity of the tender)
3. Tenders must be submitted online through e-procurement portal on or before 16.00 hours on **16-07-2022** and the opening of tenders will be as per the e-procurement portal guidelines.
4. GST Shall be Paid to the tendered amount separately
5. Other details can be seen in the tender documents.

Sl. No.	Name of the Work	Tender Put Amount in Lakhs	EMD in Lakhs	Cost of Tender form in Rs. (Non-Refundable)	Period of Completion
1	Improvements to roads, drains and other developmental works at Yelahanka old town, Maruthinagara, Sapthagiri layout Gandinagara KHB colony, Nehru nagara, shivanahalli, PDMS APTS premise and surrounding areas in ward No 01 of Yelahanka Division under Amruth Nagarothan Grants. (PACKAGE No-01)	875.00	13.15	As per E-Procurement Portal	180 days
2	Improvements to roads, drains and other developmental works at 5th phase, puttenahalli, ISAAC layout kondappa layout, kamakshamma layout, hanumappa layout, A sector and surrounding areas in ward No 02 & 04 of Yelahanka Division under Amruth Nagarothan Grants. (PACKAGE No-02)	1100.00	15.00	As per E-Procurement Portal	180 days

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

3	Improvements to roads, drains and other developmental works at Akshaya, Tirumala Nagar, Attur layout, Santhosh nagara, Muneshwara layout, Sri Sai layout, B sector and surrounding areas in ward No 03 & 04 of Yelahanka Division under Amruth Nagarothan Grants. (PACKAGE No-03)	1865.00	18.65	As per E-Procurement Portal	180 days
4	Improvements to roads, drains and other developmental works at 407,707,208 SFS, Major Akshay Girish Kumar Road, Yelahanka 4th & 5th phase and surrounding areas in ward No 01,03 & 04 of Yelahanka Division under Amruth Nagarothan Grants.(PACKAGE No-04)	875.00	13.15	As per E-Procurement Portal	180 days
5	Improvements to roads, drains and other developmental works at Shivamandira road, Mathru layout, Sharada Nagar, Judicial Layout and Surrounding Areas in ward No 02,03 & 04 of Yelahanka Division under Amruth Nagarothan Grants. (PACKAGE No-05)	1140.00	15.00	As per E-Procurement Portal	180 days
6	Construction of Synthetic tennis court, street vending zone & other developmental works at judicial layout main and cross roads, Chikkabommasandra, Someshwara Nagar, Allalasandra village and surrounding areas in ward No 04 of Yelahanka Division under Amruth Nagarothan Grants. (PACKAGE No-06)	1750.00	17.50	As per E-Procurement Portal	180 days

Calendar of events:

- Date of Pre bid meeting at the office Executive Engineer (Yelahanka Division) on **08-07-2022** at **16.00 hrs.**
- Date of Opening of bids on **18-07-2022 after 11:00 hours**

ESSENTIAL CONDITIONS:

1. The Tender Notification along with Blank Tender Form will be accessible in the website of GOK e- Procurement Platform **(Error! Hyperlink reference not valid..**
2. The interested contractors / suppliers may download the tender documents. The contractors may choose or otherwise attending the pre-bid meeting indicated in the Invitation for Tender.
3. Tender documents may be downloaded from Government of Karnataka e-Procurement website **http://eproc.karnataka.gov.in** under login for Contractors. Aspiring Bidders/Contractors who have not registered in e-procurement should register before participating through the website https://eproc.karnataka.gov.in or contact e-Procurement Helpdesk at 080 – 22485867 / 22485927.
4. The contractors shall submit the digitally signed tenders electronically on or before the date and time of submission published in the e-procurement portal along with stipulated EMD notified in the tender document.
5. The contractor / supplier shall attach scanned DD or Bank Guarantee (for EMD) along with the bid on e-procurement portal and submit the original Bank Guarantee on

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

before the last date and time notified in the Tender Document to the Tender Inviting authority.

6. The tenders will be evaluated only on confirmation of receipt of payment of EMD.
7. The Tender will remain valid for **180 Days** from the Date of Opening of Tender.
8. The Contractor is not eligible for submission of application for tender form if he has not put the tender after purchase of the tender document continuously for three times.
9. The Successful tenderer will have to execute an agreement with BBMP within **seven days** of receipt of intimation of Letter of Acceptance, failing which his tender will be summarily rejected without giving any further Notice.
10. The Contractor / Agency shall intimate the change, if any, in any of the addresses, in advance or maximum within one week of such change along with acknowledgement of noting down of such change in address from the bank, Income tax, GST authorities etc. Failure to do so liability lies on the Contractor / Agency what so ever.
11. The Work shall be commenced with all Men, Material Tools and Plants within 7 days from the Date of Work Order, failing to which it would be presumed that the Successful Tenderer is not interested in the Work and Action will be taken to get the Work executed through Alternate Agency at the risk and cost of the Former Tendered.
12. Defect Liability Period (DLP) and Maintenance Period will be as per Commissioner Order No: ಆ/ಪಿ.ಎಸ್.ಆರ್/G-5317/2012-13 ದಿನಾಂಕ: 28.09.2012
13. FSD will be refunded only after Defect Liability Period (DLP) as per Condition 12.
14. Tenders must be accompanied by Earnest Money Deposit specified for the work in the Table below. Earnest Money Deposit will have to be in any one of the forms as specified in the Tender document and shall have to be valid for **90 days** beyond the validity of the tender.
15. Frequency of the Quality tests of all the materials and other tests have to be conducted by contractor as per Specifications for Road and Bridge Works (5th Revision) and IRC:SP:11-1984 Handbook of Quality Control for Construction of Roads and Runways, IRC:SP:112-2017 Manual for Quality Control in Road and Bridge Works, IRC:SP:47-1998 Guidelines on Quality Systems for Road Bridges (Plain, Reinforced, Prestressed), RC:SP:57-2000 Guidelines for Quality Systems for Road Construction and Composite Concrete and SP:7-2005 National Building Code of India & other relevant Indian standards in his laboratory or any other Laboratory assigned by the BBMP on his own cost in presence of Engineer/ consultants appointed by BBMP.
16. As per Govt. Order No: LD 300/LET/2006, Dated: 18.07.2007, 1% of the bill amount will be deducted and remitted to Karnataka State Building & Other Construction Employees Welfare Board.
17. The Tenderers are advised to note the minimum qualification criteria specified in clause 3 of the Instructions to Tenderers to qualify for award of the contract **(Standard Tender Document KW 4** also Tenderers are advised to go through the Standard Bid Documents.
18. Any Corrigendum / Modification will be notified in the Notice Board of the Undersigned.
19. The BBMP reserves the right to accept/reject any or all tenders without assigning any reasons what so ever.
20. **Successful Tenderer should deliver to the employer a security deposit equivalent 5% of the Contract price in form of DD / Bank Guarantee in favor of Commissioner BBMP otherwise action will be initiated as per Standard Bid document clauses.**
21. **An additional security for unbalanced bids in the form of DD/ Bank Guarantee to be submitted in favor of Commissioner BBMP to the undersigned before opening of the technical bid otherwise their bids will be rejected.**

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

22. The Tender Accepting Authority shall have the power to accept or fo reject any tender without assigning any reason thereof.
23. GST will be paid to the tendered amount separately only for 2018-19 schedule of rates and for GST/VAT is included in other than 2018-19 schedule of Rates.
24. As per Government Circular No. CI 81 MMN 2014 Dt: 18.02.2014 & ಗಫೂಇ:ಡಿಸಿಬಿ/ಕಗಗು/ರಾ.ಪ.ಕೋ/2013–14 ದಿನಾಂಕ: 13.03.2014 the contractors are liable to pay royalty in terms of the contract if they are not able to produce the materials purchased document / MDP's from where they purchase.
25. Black Listed Contractors / in Govt. / Quasi Govt. / Boards / BBMP etc., are not eligible to quote, if found such Tenders will be rejected.
26. All the participants should produce all the original documents for verification whenever necessary.
27. The work shall be carried out as per the directions of the BBMP and if necessary, in coordination with BESCOM, BWSSB, Other Utility Agencies and Engineer in charge of Work.
28. No Joint Venture / Consortium is permissible.
29. The Work shall be commenced with all Men and Machinery within 7 days from the Date of Work Order, failing which it would be presumed that the Successful Tenderer is not interested in the Work and Action will be taken to get the Work executed through Alternate Agency at the risk and cost of the Former Tenderers.
30. Conditional Tenders will not be entertained and they are summarily rejected.
31. Further particulars can be had from the office of the Executive Engineer, Yelahanka Division, and BBMP during the working days between 10.00 A.M. to 5.30 P.M.
32. The Construction Debris Generated from Work Shall be dumped in Designated Dumping Yards Only.
33. If the Contractor has any liability whatsoever to the BBMP / Govt the same will be deducted from the Contractors bills.
34. Bidder shall submit the bids electronically before the stipulated date and time for the submission published in e-procurement portal. No tenders can be submitted after the due date and time as the portal will not accept late tenders.
35. The contractor / supplier can modify and correct or upload any other relevant document in tbe portal before last date and time of submission on e-portal. No modifications or withdrawal of tender is possible the closing time of the submission of the tender.
36. In the event of the specified date of tender opening being declared a holiday for the tender inviting authority, the tenders will be opened the next immediate working day.
37. As per Commissioner inter Office Note No:D/ಪಆರ್/1629/18-19 Dated:18-08-2018. The Contractors to Implement/Entrusted the works in 3 shifts round the clock.
38. Bidders Should Submit the **one set of Hard Copy with spiral Binding of all documents which are uploaded in the e-portal to this office before opening the technical bid.** Otherwise, their bid will be rejected.
39. The Bidder /Contractors should shall not Quote below the minimum labor rates prevailing @ the time of Tender Notification. If so, they shall be providing the Rate Analyses for the same. (To be uploaded in e-procurement plat form).

Sd/-
Executive Engineer
Yelahanka Division

Copy to:

1. The Chief Commissioner, BBMP for kind information.

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

2. Copy submitted to the Special Commissioner (Projects) for kind information.
3. Copy submitted to Zonal Commissioner (Yelahanka) For Kind Information.
4. Copy submitted to the Special Commissioner (Finance) & Tender bulletin officer, BBMP for requesting to publish the tender notification in tender bulletin.
5. Copy submitted to the Joint Commissioner (Yelahanka) for kind information.
6. Copy submitted to the Engineer-In-Chief for kind information.
7. Copy submitted to the Chief Engineer (Yelahanka) for kind information.
8. Copy submitted The Deputy Commissioner (Bengaluru Urban) for kind information & requested to arrange for publication and to send a copy of the same to this Office for further action.
9. Copy submitted to Chief Auditor / Chief Account officer for kind information
10. Copy submitted to A.C.F (Yelahanka) for information.
11. Copy to Public Relationship Officer, BBMP with request to make arrangements for publication of notification in two leading daily Kannada and English Bangalore based Newspapers as the case may be within next two days & requested to communicate the same to this Office as early as possible.
12. Copy to Acct. Suptd. / Cashier of Division office for Necessary Action..
13. Copy to IT Advisor with Soft copy for needful action to place in the BBMP website.
14. Copy to Store Keeper/ Records Section, Mayo Hall, Bangalore for information and need full action.
15. Copy to Assistant Executive Engineer (Yelahanka sub Division and Satellite Town Sub Division) for Information & Necessary Action.
16. Notice Board / Office Copy.

Executive Engineer
Yelahanka Division
Bruhath Bangalore Mahanagara
Palike

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

Contents

Section	Description	Page No.
1.	INVITATION FOR TENDERS (IFT)	4
2.	INSTRUCTIONS TO TENDERERS (ITT)	7
3.	QUALIFICATION INFORMATION	19
4.	FORM OF TENDER, LETTER OF ACCEPTANCE, NOTICE TO PROCEED WITH THE WORK AND AGREEMENT FORM	22
5.	CONDITIONS OF CONTRACT (CC)	25
6.	CONTRACT DATA	38
7.	SPECIFICATIONS	44
8.	DRAWINGS	44
9.	BILL OF QUANTITIES	45
10.	FORMAT OF BANK GUARANTEE FOR SECURITY DEPOSIT	54

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

A. General

1. **Scope of Tender**

1.1 **The Executive Engineer, Yelahanka Division, BBMP** (Referred to as Employer in these documents) invites tenders following Two Cover tender procedure, from eligible Tenderers, for the construction of works (as defined in these documents and referred to as "the works") detailed in the Table given in the Invitation for Tenders (IFT). The Tenderers may submit tenders for any or all of the works detailed in the table given in IFT.

2. **Eligible Tenderer's:**

2.1 Tenderers shall not be under a declaration of ineligibility for corrupt and fraudulent practices issued by the Government of Karnataka / BBMP

2.2 **Tenders from Joint ventures are not acceptable.**

3. **Qualification of the Tenderer:**

3.1 All Tenderers shall provide the requested information accurately and in sufficient detail in Section 3: Qualification information.

3.2 To qualify for award of this contract, each Tenderer in its name should have in the last five years (i.e. 2017-18 to 2021-22)

(a) achieved in at least two financial years a minimum financial turnover (in all classes of civil engineering construction works only) of **Rs.37.30 Crores**

(b) satisfactorily completed (at least 50% of the contract value) as prime contractor, at least one similar work such as Improvements of Roads and Drains of value not less than **Rs. 950.00 Lakhs**

(c) executed in any one year the following minimum quantities of work:[1]

Sl. No	Description	Unit	Quantity
1	Earthwork excavation	Cum	10330
2	PCC/RCC	Cum	4260
3	TMT Steel	Tonne	110
4	Pre Cast Covering Slabs	Sqm	6460
5	Pre Cast Kerb Stone	Nos	7000
6	Heavy duty cobble stones	Sqm	4040
7	M30	Cum	390
8	BM & BC	Cum	3640
9	Wet Mix Macadam	Cum	4490

Note: Certified Contractors Bill Copies shall be uploaded (Admitted Bill Copies)

(d) The Tenderer or his identified sub-contractor should possess required valid electrical license for executing building electrification works and should have executed similar electrical works totaling Rs. ..... *(usually not less than 50% of the electrical works)** in any one year;[2]

(e) The Tenderer or his identified sub-contractor should possess valid license for executing water supply/sanitary engineering works and should have executed similar water supply/sanitary engineering works totaling Rs..... *(usually not less than 50% of the water supply/sanitary engineering works)** in any one year;[3]

3.3 Each Tenderer should further demonstrate:

[1] Specify the principal items of works to be executed under this contract
[2] This is for building works. Appropriately change for other works.
[3] This is for building works. Appropriately change for other works.

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

4.1 Each tenderer shall submit only one tender for one package. A tenderer who submits or participates in more than one Tender (other than as a sub-contractor or in cases of alternatives that have been permitted or requested) will cause all the proposals with the Tenderer's participation to be disqualified.

5. **Cost of Tendering:**

5.1 The tenderer shall bear all costs associated with the preparation and submission of his tender, and the Employer will in no case be responsible and liable for those costs.

6. **Site visit:**

6.1 The Tenderer at his own responsibility and risk is encouraged to visit and examine the Site of Works and its surroundings and obtain all information that may be necessary for preparing the Tender and entering into a contract for construction of the Works. The cost of visiting the Site shall be at the Tenderer's own expense.

B. Tender documents

7. **Content of Tender documents**

7.1 The set of tender documents shall have all the Sections given in Page 2.

7.2 Both the sets should be completed and returned with the tender.

8. **Clarification of Tender Documents**

8.1 A prospective tenderer requiring any clarification of the tender documents may notify the Employer in writing or by cable (hereinafter "cable" includes telex and facsimile) at the Employer's address indicated in the invitation to tender. The Employer will respond to any request for clarification which he receives earlier than 15 days prior to the deadline for submission of tenders. Copies of the Employer's response will be forwarded to all purchasers of the tender documents, including a description of the enquiry but without identifying its source.

8.2 **Pre-tender meeting:**

8.2.1 The tenderer or his authorized representative is invited to attend a pre-tender meeting which will take place at **The Office of the Executive Engineer , Yelahanka Division, Bangalore – 560064 on 08-07-2022 at 15.00 Hours**

8.2.2 The purpose of the meeting will be to clarify issues and to answer questions on any matter that may be raised at that stage

8.2.3 The tenderer is requested to submit any questions in writing or by cable to reach the Employer not later than **2 days before Pre bid meeting.**

8.2.4 Minutes of the meeting, including the text of the questions raised (without identifying the source of enquiry) and the responses given will be transmitted without delay to all purchasers of the tender documents. Any modification of the tender documents listed in Sub-Clause 7.1 which may become necessary as a result of the pre-tender meeting shall be made by the Employer exclusively through the issue of an Addendum pursuant to Clause 9 and not through the minutes of the pre-tender meeting.

8.2.5 Non-attendance at the pre-tender meeting will not be a cause for disqualification of a tenderer.

9. **Amendment of Tender documents**

9.1 Before the deadline for submission of tenders, the Employer may modify the tender documents by issuing addenda.

9.2 Any addendum thus issued shall be part of the tender documents and shall be communicated in writing or by cable to all the purchasers of the tender documents.

9.3 To give prospective Tenderers reasonable time in which to take an addendum into account in preparing their tenders, the Employer shall extend as necessary the deadline for submission of tenders, in accordance with Sub-Clause 16.2 below.

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

e) Fixed Deposit Receipt (FDR) subject to the following condition

- Maturity date of FDRs issued by the Bank should be beyond the date expected date of finalization of the tender.

Earnest money deposit will have to be in any one of the forms as specified in the Tender document and as per circular PWD:15:ITC:2008/2009 Dated:02-12-2010 (Minimum of Rs.1,00,000/- through e-payment under of the following i.e., online / RTGS / NEFT / OTC and the balance by bank guarantee/FDR issued by Nationalized/Scheduled Bank and shall have to be valid for 90 days beyond the validity of the tender.

As per Circular: PWD:15:ITC:2008/2009 Dated:02-12-2010 the Tenderer shall submit the ORIGINAL BG/FDR for Part EMD on or before the Opening of Technical Bid, if failed to submit, the bid will be rejected and the initial amount deposited through e-procurement will be forfeited and further their names will be proposed for Black Listing if resorted repeatedly.

13.2 Instruments having fixed validity issued as earnest money deposit for the tender shall be valid for 45 days **beyond** the validity of the tender.

13.3 Any tender not accompanied by an acceptable earnest money deposit and not secured as indicated in Sub-Clauses 13.1 and 13.2 above shall be rejected by the Employer as non-responsive.

13.4 The earnest money deposit of unsuccessful Tenderers will be returned within 30 days of the end of the tender validity period specified in Sub-Clause 12.1.

13.5 The earnest money deposit of the successful Tenderer will be discharged when the Tenderer has signed the Agreement and furnished the required Performance Security.

13.6 The earnest money deposit may be forfeited

(a) if the Tenderer withdraws the Tender after tender opening during the period of tender validity;

(b) if the Tenderer does not accept the correction of the Tender Price, pursuant to Clause 24; or

(c) in the case of a successful Tenderer, if the Tenderer fails within the specified time limit to

(i) Sign the Agreement, or

(ii) Furnish the required Security deposit

14. Format and signing of Tender

14.1 The Tenderer shall prepare one original and a copy of the documents comprising the Tender as described in Clause 10 of these *Instructions to Tenderers*, and clearly marked **"ORIGINAL"** and **"COPY"** as appropriate. In the event of discrepancy between them, the original shall prevail.

14.2 The original and a copy of the Tender shall be typed or written in indelible ink and shall be signed by a person or persons duly authorized to sign on behalf of the Tenderer. All pages of the tender where entries or amendments have been made shall be initialed by the person signing the tender.

14.3 The Tender shall contain no alterations or additions, except those to comply with instructions issued by the Employer, or as necessary to correct errors made by the Tenderer, in which case such corrections shall be initialed by the person signing the Tender.

D. Submission of Tenders

15. Sealing and marking of tenders

15.1 The Tenderer shall seal the original and a copy of the Tender in separate envelopes, duly marking the envelopes as **"ORIGINAL"** and **"COPY"**. These envelopes (called as inner envelopes) shall then be put inside one outer envelope.

15.2 The inner and outer envelopes shall

(a) be addressed to the Employer at the following address:

Office of the Executive Engineer
Yelahanka Division
CMC Road, Yelahanka old town Bangalore – 560064.

(insert address of office for Tender submission), and

(b) bear the following identification:

Tender for .....[name of contract]

Tender Reference No.....[insert number]

DO NOT OPEN BEFORE.....[time and date for tender opening per Clause 19]

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

25.5 If the tender of the successful tenderer is seriously unbalanced in relation to the Employer's estimate of the cost of the work to be performed under the contract, the Employer may require the Tenderer to produce detailed price analyses for any or all items of the Bill of Quantities, to demonstrate the internal consistency of those prices with the construction methods and schedule proposed. After evaluation of the price analyses, the Employer may require that the amount of the performance security set forth in Clause 29 be increased at the expense of the successful Tenderer to a level sufficient to protect the Employer against financial loss in the event of default of the successful under the contract.

F. Award of Contract

26. Award criteria

26.1 Subject to Clause 27, the Employer will award the Contract to the Tenderer whose Tender has been determined to be substantially responsive to the Tender documents and who has offered the lowest evaluated Tender Price, provided that such Tenderer has been determined to be (a) eligible in accordance with the provisions of Clause 2, and (b) qualified in accordance with the provisions of Clause 3.

27. Employer's right to accept any Tender and to reject any or all Tenders

27.1 Notwithstanding Clause 26, the Employer reserves the right to accept or reject any Tender, and to cancel the Tender process and reject all Tenders, at any time prior to the award of Contract, without thereby incurring any liability to the affected Tenderer or Tenderers or any obligation to inform the affected Tenderer or Tenderers of the grounds for the Employer's action.

28. Notification of award and signing of Agreement

28.1 The Tenderer whose Tender has been accepted will be notified of the award by the Employer prior to expiration of the Tender validity period by cable, telex, e-mail or facsimile confirmed by registered letter. This letter (hereinafter and in the *Conditions of Contract* called the "Letter of Acceptance") will state the sum that the Employer will pay the Contractor in consideration of the execution, completion, and maintenance of the Works by the Contractor as prescribed by the Contract (hereinafter and in the Contract called the "Contract Price").

28.2 The notification of award will constitute the formation of the Contract, subject only to the furnishing of Security deposit in accordance with the provisions of Clause 29.

28.3 The Agreement will incorporate all agreements between the Employer and the successful Tenderer. It will be kept ready for signature of the successful Tenderer in the office of Employer within 30 days following the notification of award along with the Letter of Acceptance. Within 20 days of receipt, the successful Tenderer will sign the Agreement and deliver it to the Employer.

28.4 Upon the furnishing by the successful Tenderer of the Performance Security, the Employer will promptly notify the other Tenderers that their Tenders have been unsuccessful.

29. Security deposit

29.1 Within 20 days of receipt of the Letter of Acceptance, the successful Tenderer shall deliver to the Employer a Security deposit in any of the forms given below for an amount equivalent to 3% of the Contract price plus additional security for unbalanced tenders in accordance with Clause 25.5 of ITT and Clause 44 of the Conditions of Contract for all works. :

- Banker's cheque/Demand draft,/Pay Order in favour of Commissioner BBMP payable at Bangalore or
- **A Bank Guarantee in the form given in Section 10; or**
- **Special Small savings instruments pledged to Commissioner, BBMP / Executive Engineer – Yelahanka Division, BBMP**

29.2 If the security deposit is provided by the successful Tenderer in the form of a Bank Guarantee, it shall be issued either by a Nationalized/Scheduled bank.

29.3 The security deposit if furnished in cash or demand draft can, if requested, be converted to interest bearing securities at the cost of the contractor.

29.4 Failure of the successful Tenderer to comply with the requirements of Sub-Clause 29.1 shall constitute sufficient grounds for cancellation of the award and forfeiture of the Earnest money deposit.

30 Advance Payment and Security:

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

1.5 Information on works for which Tenders have been submitted and works which are yet to be completed as on the date of this Tender.

(A) Existing commitments and on-going works:

Description of Work	Place & State	Contract No. & Date	Name And Address of Employer	Value of Contract (Rs. lakhs)	Stipulated period of completion	Value of works remaining to be completed (Rs. lakhs) Attach Certificates from Engineers -in-Charge	Anticipated date of completion
1	2	3	4	5	6	7	8

(B) Works for which Tenders already submitted:

Description of Work	Place & State	Name and Address of Employer	Estimated value of works (Rs. lakhs)	Stipulated period of completion	Date when decision is expected	Remarks if any
1	2	3	4	5	6	7

1.6. The following items of equipment are considered essential for successfully carrying out the works. The Tenderer should furnish all the information listed below.

Item of Equipment	Requirement[8]		Owned	Owned and available		
	No.	Capacity		Number/ Capacity	Age/ condition	Remarks

1.7 Reports on the financial standing of the tenderer, such as profit and loss statements and auditor's reports for the last five years;

1.8 Qualification and experience of the key technical and management personnel in permanent employment with the tenderer and those that are proposed to be deployed on this contract, if awarded.

1.9. Name, address, and telephone, telex, and fax numbers of the Tenderers' bankers who may provide references if contacted by the Employer.

1.10 Evidence of access to financial resources to meet the qualification requirement specified in ITT Clause3.3 (b): Cash in hand, Letter of Credit etc. List them below and attach certificate from the Banker in the suggested format as under:

BANKER'S CERTIFICATE

This is to certify that M/s. ..... is a reputed company with a good financial standing. If the contract for this work, namely ..... (*name of the work*) is awarded to the above firm, we shall be able to provide overdraft/credit facilities to the extent of Rs. ..... to meet the working capital requirements for executing the above contract.

Name of the Bank, Senior Bank Manger
with Signature

Address:.....

1.11 Proposals for subcontracting components of works amounting to more than 20% of the contract price.

Item of Work	Value of Sub-Contract	Identified Sub-Contractor (Name and address)	Experience of similar work (Attach certificates from the respective Employers.)
1	2	3	4

1.12 Information on litigations in which the Tenderer is involved:

[8] The item of equipment, required number and capacity should match with those specified in ITT Clause 3.3

(a)
CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

Letter of Acceptance

(letterhead paper of the Employer) .....[date]

To:

.....

.....[name and address of the Contractor]

Dear Sirs,

This is to notify you that your Tender dated ..... for execution of the .....

..... *[name of the contract and identification number, as given in the Instructions to Tenderers]* for the Contract Price of Rupees ..... (.....) [amount in words and figures], as corrected and modified in accordance with the Instructions to Tenderers is hereby accepted by our Agency.

You are hereby requested to furnish Security deposit plus additional security for unbalanced tenders in terms of Clause 25.5 of ITT, in the form detailed in Clause 29.1 of ITT for an amount of Rs ..... within 20 days of the receipt of this letter of acceptance valid up to 30 days from the date of expiry of Defects Liability Period i.e. up to ..... and sign the contract, failing which action as stated in Para 29.4 of ITT will be taken.

Yours faithfully,

Authorized Signature

Name and Title of Signatory

Name of Agency

Issue of Notice to proceed with the work

(letterhead of the Employer) .....(date)

To

.....

.....

..... (name and address of the Contractor)

Dear Sirs:

Pursuant to your furnishing the requisite security deposit as stipulated in ITT Clause 29.1 and signing of the contract agreement for the construction of ..... (name of the work) a Tender Price of Rs..... , you are hereby instructed to proceed with the execution of the said works in accordance with the contract documents.

Yours faithfully,

(Signature, name and title of signatory authorized to sign on behalf of Employer)

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

SECTION 5: CONDITIONS OF CONTRACT

Table of Contents

		Page No.
A.	**General**	25
	1. Definitions	25
	2. Interpretation	26
	3. Law governing contract	26
	4. Employers decisions	26
	5. Delegation	26
	6. Communications	26
	7. Subcontracting	26
	8. Other Contractors	26
	9. Personnel	26
	10. Employer's and Contractor's risks	27
	11. Employer's risks	27
	12. Contractor's risks	27
	13. Insurance	27
	14. Site Investigation Report	27
	15. Query about Contract Data	
	16. Contractor to construct the Works	28
	17. The Works to be completed by Intended Completion Date28	
	18. Approvals by the Employer	28
	19. Safety	28
	20. Discoveries	28
	21. Possession of the Site	28
	22. Access to the Site	28
	23. Instructions	
	24. Procedure for resolution of disputes 28	
B.	**Time Control**	29
	25. Program	29
	26. Extension of the Intended Completion Date	
	27. Delays ordered by the Employer 29	29
	28. Management meetings	
C.	**Quality Control**	29
	29. Identifying defects	29
	30. Tests	29
	31. Correction of defects	30
	32. Uncorrected defects	
D.	**Cost Control**	30
	33. Bill of Quantities (BOQ)	30
	34. Variations	30
	35. Payment for Variations 31	
	36. Submission of bills for payment	31
	37. Payments	31
	38. Compensation events	31
	39. Tax	32
	40. Price Adjustment	32
	41. Liquidated damages	32
	42. Advance Payments	32
	43. Securities	32
	44. Cost of repairs	
E	**Finishing of Contract**	32
	45. Completion	32
	46. Taking Over	32
	47. Final account	33
	48. As built drawings and/or Operating and Maintenance Manuals	33
	49. Termination	33
	50. Payment upon termination	34
	51. Property	34
	52. Release from performance	
F	**Special Conditions of Contract**	34

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

(8) Bill of quantities and
(9) any other document listed in the Contract Data as forming part of the Contract.

3. **Law governing contract**

3.1 The law governing the Contract is the Laws of India supplanted by the Karnataka Local Acts.

4. **Employer's decisions**

4.1 Except where otherwise specifically stated, the Employer will decide contractual matters between the Employer and the Contractor.

5. **Delegation**

5.1 The Employer may delegate any of his duties and responsibilities to other people after notifying the Contractor and may cancel any delegation after notifying the Contractor.

6. **Communications**

6.1 Communications between parties which are referred to in the conditions are effective only when in writing. A notice shall be effective only when it is delivered (in terms of Indian Contract Act).

7. **Subcontracting (Deleted)**

7.1 Deleted.

8. **Other Contractors**

8.1 The Contractor shall cooperate and share the Site with other contractors, public authorities, utilities, and the Employer.

9. **Personnel**

9.1 The Contractor shall employ the technical personnel (of number and qualifications) as may be stipulated by GOK from time to time during the execution of the work. The technical staff so employed shall be available at site as may be stipulated by the Employer.

9.2 If the Employer asks the Contractor to remove a person who is a member of the Contractor's staff or his work force stating the reasons, the Contractor shall ensure that the person leaves the Site within seven days and has no further connection with the work in the Contract.

10. **Employer's and Contractor's risks**

10.1 The Employer carries the risks which this Contract states are Employer's risks, and the Contractor carries the risks which this Contract states are Contractor's risks.

11. **Employer's risks**

11.1 The Employer is responsible for the excepted risks which are:
(a) rebellion, riot commotion or disorder unless solely restricted to employees of the Contractor or his Sub-Contractors arising from the conduct of the Works; or
(b) a cause due solely to the design of the Works, other than the Contractor's design; or
(c) any operation of the forces of nature (in so far as it occurs on the Site) which an experienced contractor:
  (i) could not have reasonably foreseen; or
  (ii) could reasonably have foreseen, but against which he could not reasonably have taken at least one of the following measures;
    (A) prevent loss or damage to physical property from occurring by taking appropriate measures or
    (B) insure against such loss or damage

12. **Contractor's risks**

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

19. Safety

19.1 The Contractor shall be responsible for the safety of all activities on the Site.

20. Discoveries

20.1 Anything of historical or other interest or of significant value unexpectedly discovered on the Site is the property of the Employer. The Contractor is to notify the Employer of such discoveries and carry out the Employer's instructions for dealing with them.

21. Possession of the Site

21.1 The Employer shall give possession of all parts of the Site to the Contractor. If possession of a part is not given by the date stated in the Contract Data the Employer is deemed to have delayed the start of the relevant activities and this will be Compensation Event.

22. Access to the Site

22.1 The Contractor shall allow the Employer and any person authorized by the Employer access to the Site, to any place where work in connection with the Contract is being carried out or is intended to be carried out and to any place where materials or plant are being manufactured / fabricated / assembled for the works.

23. Instructions

23.1 The Contractor shall carry out all instructions of the Employer which comply with the applicable laws where the Site is located.

24. Procedure for resolution of Disputes:

24.1 If the Contractor is not satisfied with the decision taken by the Employer, the dispute shall be referred by either party to Arbitration within 30 days of the notification of the Employer's decision.

24.2 If neither party refers the dispute to Arbitration within the above 30 days, the Employer's decision will be final and binding.

24.3 The Arbitration shall be conducted in accordance with the arbitration procedure stated in the Special Conditions of Contract.

B. Time Control

25. Program

25.1 Within the time stated in the Contract Data the Contractor shall submit to the Employer for approval a Program showing the general methods, arrangements, order, and timing for all the activities in the Works.

25.2 The Employer's approval of the Program shall not alter the Contractor's obligations. The Contractor may revise the Program and submit it to the Employer again at any time. A revised Program is to show the effect of Variations and Compensation Events.

26. Extension of the Intended Completion Date

26.1 The Employer shall extend the Intended Completion Date if a Compensation Event occurs or a Variation is issued which makes it impossible for Completion to be achieved by the Intended Completion Date.

26.2 The Employer shall decide whether and by how much to extend the Intended Completion Date within 21 days of the Contractor asking the Employer for a decision upon the effect of a Compensation Event or Variation and submitting full supporting information.

27. Delays ordered by the Employer

27.1 The Employer may instruct the Contractor to delay the start or progress of any activity within the Works.

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

shall be carried out as though there is no variation. In case variation is approved it shall be accompanied by BOQ, failing which the contractor shall be responsible for deviation if any. Further, approval of Govt. / BBMP has to be obtained for the variation exceeding 5%.

35. Payments for Variations

35.1 Payment for increase in the quantities of an item in the BOQ up to 25% of that provided in the Bill of Quantities shall be made at the rates quoted by the Contractor.

35.2 For quantities in excess of 125% of the tendered quantity of an item as given in the BOQ, the Contractor shall be paid at the rate entered in or derived from in the Schedule of Rates (applicable for the area of the work and current at the time of award of contract) plus or minus the overall percentage of the original tendered rates over the current Schedule of Rates prevalent at the time of award of contract.

35.3 If there is no rate for the additional, substituted or altered item of the work in the BOQ, efforts would be made to derive the rates from those given in the BOQ or the Schedule of Rates (applicable for the area of the work and current at the time of award of contract) and if found feasible the payment would be made at the derived rate for the item plus or minus the overall percentage of the original tendered rates over the current Schedule of Rates prevalent at the time of award of contract

35.4 If the rates for additional, substituted or altered item of work cannot be determined either as at 35.1 or 35.2 or 35.3 above, the Contractor shall be requested to submit his quotation for the items supported by analysis of the rate or rates claimed, within 7 days.

35.5 If the Contractor's quotation is determined unreasonable, the Employer may order the Variation and make a change to the Contract Price which shall be based on Employer's own forecast of the effects of the Variation on the Contractor's costs.

35.6 If the Employer decides that the urgency of varying the work would prevent a quotation being given and considered without delaying the work, no quotation shall be given and the Variation shall be treated as a Compensation Event.

35.7 Under no circumstances the Contractor shall suspend the work on the plea of non-settlement of rates for items falling under this Clause.

36. Submission of bills for payment

36.1 The Contractor shall submit to the Employer monthly bills of the value of the work completed less the cumulative amount paid previously.

36.2 The Employer shall check the Contractor's bill and determine the value of the work executed which shall comprise of (i) value of the quantities of the items in the BOQ completed and (ii) valuation of Variations and Compensation Events.

36.3 The Employer may exclude any item paid in a previous bill or reduce the proportion of any item previously paid in the light of later information.

37. Payments

37.1 Payments shall be adjusted for deductions for advance payments other than recoveries in terms of contract and taxes, at source, as applicable under the law. The Employer shall pay the Contractor the within 60 days of submission of bill. The contractor shall be liable to pay liquidated damages for shortfall in progress. For progress beyond the agreed programme payment is subject to availability of the grants.

37.2 Items of the Works for which no rate or price has been entered in will not be paid for by the Employer and shall be deemed covered by other rates and prices in the Contract.

38. Compensation events

38.1 The following are Compensation events unless they are caused by the Contractor:

(a) The Employer does not give access to a part of the Site by the Site Possession Date stated in the Contract Data.

(b) The Employer orders a delay or does not issue drawings, specifications or instructions required for execution of works on time.

(c) The Employer instructs the Contractor to uncover or to carry out additional tests upon work which is then found to have no Defects.

(d) The Employer gives an instruction for dealing with an unforeseen condition, caused by the Employer, or additional work required for safety or other reasons.

(e) The effect on the Contractor of any of the Employer's Risks.

(f) The Employer unreasonably delays issuing a Certificate of Completion.

(g) Other Compensation Events listed in the Contract Data or mentioned in the Contract.

of expiry of Defects Liability Period and the additional security for unbalanced tenders shall be valid until a date 30 days from the date of issue of the certificate of completion.

44. **Cost of Repairs:**

44.1 Loss or damage to the Works or Materials to be incorporated in the Works between the Start Date and the end of the Defects Correction periods shall be remedied by the Contractor at the Contractor's cost if the loss or damage arises from the Contractor's acts or omissions.

E. Finishing the Contract

45. **Completion**

45.1 The Contractor shall request the Employer to issue a Certificate of Completion of the Works and the Employer will do so upon deciding that the Work is completed.

46. **Taking over**

46.1 The Employer shall take over the Site and the Works within seven days of issuing a certificate of Completion.

47. **Final account**

47.1 The Contractor shall supply to the Employer a detailed account of the total amount that the Contractor considers payable under the Contract before the end of the Defects Liability Period. The Employer shall issue a Defect Liability Certificate and certify any final payment that is due to the Contractor within 90 days of receiving the Contractor's account if it is correct and complete. If it is not, the Employer shall issue within 90 days a schedule that states the scope of the corrections or additions that are necessary. If the Final Account is still unsatisfactory after it has been resubmitted, the Employer shall decide on the amount payable to the Contractor and make payment within 60 days of receiving the Contractor's revised account.

48. **As built drawings and /or Operating and Maintenance Manuals**

48.1 If "as built" (*Completion drawings*) Drawings and/or operating and maintenance manuals are required, the Contractor shall supply them by the dates stated in the Contract Data.

48.2 If the Contractor does not supply the Drawings by the dates stated in the Contract Data, or they do not receive the Employer's approval, the Employer shall withhold the amount stated in the Contract Data from payments due to the Contractor.

49. **Termination**

49.1 The Employer may terminate the Contract if the other party causes a fundamental breach of the Contract.

49.2 Fundamental breaches of Contract include, but shall not be limited to the following:

(a) The Contractor stops work for 45 days when no stoppage of work is shown on the current Program and the stoppage has not been authorized by the Employer;

(b) Deleted

(c) The Contractor becomes bankrupt or goes into liquidation other than for a reconstruction or amalgamation;

(d) Deleted.

(e) the Employer gives Notice that failure to correct a particular Defect is a fundamental breach of Contract and the Contractor fails to correct it within a reasonable period of time determined by the Employer;

(f) The Contractor does not maintain a security which is required;

(g) the Contractor has delayed the completion of works by the number of days for which the maximum amount of liquidated damages can be paid as defined in the Contract data; and

(h) If the Contractor, in the judgment of the Employer has engaged in corrupt or fraudulent practices in competing for or in the executing the Contract.
For the purpose of this paragraph : "corrupt practice" means the offering, giving, receiving or soliciting of any thing of value to influence the action of a public official in the procurement process or in contract execution. "Fraudulent practice" means a misrepresentation of facts in order to influence a procurement process or the execution of a contract to the detriment of the Borrower, and includes collusive practice among Tenderers (prior to or after Tender submission) designed to establish Tender prices at artificial non-competitive levels and to deprive the Borrower of the benefits of free and open competition."

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

amount of security deposit. The Employer shall also have right to recover from the Contractor any sum required or estimated to be required for making good the loss or damage suffered by the Employer.

The employees of the Contractor in no case shall be treated as the employees of the Employer at any point of time

3. **Protection of Environment:**

The contractor shall take all reasonable steps to protect the environment on and off the Site and to avoid damage or nuisance to persons or to property of the public or others resulting from pollution, noise or other causes arising as a consequence of his methods of operation. During continuance of the contract, the contractor shall abide at all times by all existing enactments on environmental protection and rules made there under, regulations, notifications and bye-laws of the State or Central Government, or local authorities and any other law, bye-law, regulations that may be passed or notification that may be issued in this respect in future by the State or Central Government or the local authority.

4. **Arbitration (Clause 24)**

4.1 The procedure for arbitration shall be as follows:

(a) In case of dispute or difference arising between the Employer and the Contractor relating to any matter arising out of or connected with this agreement it shall be settled in accordance with the Arbitration and Conciliation Act 1996. The disputes or differences shall be referred to a Sole Arbitrator. The Sole Arbitrator shall be appointed by agreement between the parties, failing such agreement, by the Appointing Authority (any one of the Organizations as per list enclosed in Annexure)

(b) Arbitration proceedings shall be held at ..... Karnataka state (to be filled in by the Employer before issue of the Tender Documents),

(c) The cost and expenses of arbitration proceedings will be paid as determined by the Arbitrator. However the expenses incurred by each party in connection with the preparation, presentation, etc , shall be borne by each party itself.

5. In the case of the death of a Contractor after executing the agreement / commencement of the work, his legal heir, if an eligible registered Contractor and willing can execute and complete the work at the accepted tender rates irrespective of the cost of the work

6. The Contractor should produce invoice for procurement of Bitumen, Steel, HDPE ducts, Geo-textile material along with bills. No payments will be made without such invoices.

7. Mix Designs for Concrete and Asphalt work should be got approved by Chief Engineer before commencement of Work.

8. 63/51 mm Double Walled Corrugated HDPE Duct should have the inner layer as silicore marking the duct manufacturer and also size of the duct. The Duct should conform to ISO Certification and the colour of duct should be orange or blue for better identity

9. The Contractor shall provide One four wheeler along with driver, fuel expenses to Project Engineers in-charge of work to facilitate and co-ordinate the supervision of the work.

10. The Contractor shall establish field lab and field office to facilitate quality assurance of execution of works.

11. The hot mix plant unit should be within the radius of 40km from Vidhanasoudha, Bangalore

12. The availability of hot mix plant and ownership will be ascertained by physical inspection at the time of technical evaluation by the evaluation authority

13. GST Shall be Paid to the Tendered Amount Separately

14. Tenderer should have Registered with EPF and ESI authorities. Certification should be produced at the time of Tendering OR else being entering into the Agreement.

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

The Intended Completion Date for the whole of the Works is 06 months[12] with the following milestones [17, 26]

Milestone dates:
Physical works to be completed Period from the date of issue of Notice to proceed with the work

Milestone 1 i.e Financial Progress for Rs.621.00 Lakhs within 02 Months from the date of work order (33%)
Milestone 2 i.e Financial Progress for Rs.1243.33 Lakhs within 04 Months from the date of work order (66%)

Milestone 3 i.e Financial Progress for Rs.1865.00 Lakhs within 06 Months from the date of work order (100%)

[21]

The Site Possession Date is:[13] **Date of work order**

[1.1]

The Site is located at **Yelahanka Division Limits**
and is defined in drawings

The Defects Liability Period is **3 Years** for roads asphalted with both BM/DBM and BC [14] [31]
The Defects Liability Period is **1 Year** for roads asphalted with only BC [15]
The Defects Liability Period is **1 Year** for civil works

[13]

Insurance requirements are as under:

	Type of Cover	Minimum cover for Insurance[16]
(i)	Works of Plant and materials	The sum stated in the Agreement plus 20%
(ii)	Loss or damage to equipment	Full replacement cost
(iii)	Loss or damage to property of Third Party	Full replacement cost
(iv)	Personal injury or death insurance (a) for Third Party[17]	
	(b) for Contractor's employees or labour	In accordance with the statutory requirements applicable to Karnataka

Price Adjustment Formula,[18] [40]

R= Value of work as defined in Clause 40.1 of Conditions of Contract.

Adjustment for labour component:

[12] At the time of preparation of the tender document give the period required for completion of whole work and the milestones. When the Agreement is drawn after award of contract the dates can be put in.
[13] At the time of preparation of the tender document give the period after the issue of work order, when the site would be made available to the contractor, for example 'one week after the issue of work order'
[14] The period should depend up on the period required for testing of the work. In case of building it could be 12 months (passing of one rainy season); for pipe laying work, tanks, water retaining structures, the time required for testing; for canals, lining works, the passing of one monsoon or running of canal whichever is lower; roads and highways passing of one monsoon (12 months)
[15] The period should depend up on the period required for testing of the work. In case of building it could be 12 months (passing of one rainy season); for pipe laying work, tanks, water retaining structures, the time required for testing; for canals, lining works, the passing of one monsoon or running of canal whichever is lower; roads and highways passing of one monsoon (12 months)
[16] Employer to specify as per requirement. Exclusions if any should also be specified.
[17] Specify an appropriate figure. For normal works it could be Rs.20 lakhs to cover 4 persons @Rs.5 lakhs each.
[18] The Formula has some normal components. It should be changed if need be to suit the nature of the work.

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

(iv) Price adjustment for increase or decrease in the cost of bitumen shall be paid in accordance with the following formula:

$$V_B = 0.85 \times P_B/100 \times R \times (B_t - B_o)/B_o \text{ , Where}$$

V_B = Increase or decrease in the cost of work during the quarter under consideration due to changes in the rate for bitumen.

B_o = The official retail price of bitumen at the IOC /HPCL/BPL or any other depot at .....[23] on the day 30 days prior to the date of opening of Bids.

B_t = The official retail price of bitumen at the IOC/HPCL/BPL or any other depot at ..... for the 15th day of the middle calendar month of the quarter under consideration.

P_B = Percentage of bitumen component of the work.

Adjustment of Fuel and Lubricant component.

(v) Price adjustment for increase or decrease in cost of Fuel and Lubricants shall be paid in accordance with the following formula:

$$V_F = 0.85 \times P_F/100 \times R \times (F_t - F_o)/F_o, \text{ Where.}$$

V_F = Increase or decrease in the cost of work during the quarter under consideration due to changes in the rates for Fuel and Lubricants.

F_o = The official retail price of High Speed Diesel (HSD) at the IOC/HPCL/BPL or other consumer pump at Bangalore on the day 30 days prior to the date of opening of Bids.

F_t = The official retail price of HSD at the IOC/HPCL/BPL or other consumer pump at Bangalore for the 15th day of the middle calendar month of the quarter under consideration.

P_F = Percentage of Fuel and Lubricant component of the work.

Note: For the application of this Clause the price of HSD[24] has been chosen to represent Fuel and Lubricant Group

Adjustment for Plant and Machinery Spares Component.

(vi) Price adjustment for increase or decrease in the cost of plant and machinery spares procured by the contractor shall be paid in accordance with the following formula:

$$V_P = 0.85 \times P_P/100 \times R \times (P_t - P_o)/P_o \text{ , Where}$$

V_P = Increase or decrease in the cost of work during the quarter under consideration due to changes in the rates for plant and machinery spares.

P_o = The all India average wholesale price index for Heavy machinery and parts for the quarter preceding the date of opening of bids, as published by the Office of the Economic Advisor, Ministry of Commerce and Industry, Government of India, New Delhi

P_t = The all India average wholesale price index for Heavy machinery and parts for the quarter under consideration as published by the Office of the Economic Advisor, Ministry of Commerce and Industry, Government of India, New Delhi

P_B = Percentage of Plant and Machinery Spares component of the work.

Note: For the application of this Clause index of Heavy Machinery and Parts[25] has been chosen to represent the Plant and Machinery Spares Group.

Adjustment for Other materials.:

(vii) Price adjustment for increase or decrease in the cost of other materials other than cement, steel, bitumen and Fuel and Lubricants[26], procured by the contractor shall be paid in accordance with the following formula:

---

[23] Insert the nearest location of POL Depot

[24] This could be appropriately changed to any other item depending on the nature of work.

[25] This could be appropriately changed to any other item depending on the nature of the work.

of all such payments to the Contractor has reached not less than 15 percent of the Contract Price or Three [33] months from the date of payment of first installment of advance, whichever period concludes earlier, and shall be made at the rate of 7.5% percent of the amounts of all Interim Payment Certificates until such time as the loan has been repaid, always provided that the loan shall be completely repaid prior to the expiry of the original time for completion pursuant to Clauses 17 and 26.

[34]The date by which "as-built"[35] **drawings (in scale 1:1000[36])** in 2 sets are required is within 30 days of issue of certificate of completion of Whole or Section of the Work as the case may be. [48]

[37]The date by which Operating and Maintenance Manuals are required is within 30 days of issue of certificate of completion of Whole or Section of the Work as the case may be.

The amount to be withheld for failing to supply "as built" drawings or supply of Operation and Maintenance Manuals by the date required is **Rs 1,00,000/-**

(The amount should be sufficient to get the completion drawings or Operating and Maintenance Manuals prepared by alternative agency in case the contractor fails to submit.) [48]

The following events shall also be fundamental breach of the contract. [49.2]

1. The contractor has contravened Sub-clause 7.1 and Clause 9 of CC.

The percentage to apply to the value of the work not completed representing the Employer's Additional cost for completing the Works shall be 30 percent (30%). [50.1]

(Change if need be. It should be sufficient to get the balance of works completed by alternative agency.)

SECTION 7: SPECIFICATIONS

As per specifications mentioned in BOQ

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

Bruhat Bangalore Mahanagara Palike
Excecutive Engineer Yelahanka Division

Name of Work:Improvements To Roads and Drains And Other Developmental Works At Akskshaya,Thirumalanagar,Muneshwara Layout,Sri Sai Layout, B Sector And Surrounding Areas in Ward No-03 And 04 Of Yelahanka Division Under Amruth Nagarothan Grants[PACKAGE NO-03]

Schedule-B

Item No	Description of work	Unit	Quantity	Rate as per estimate in Rs.	
				In Figures	In Words
1	Removing and Resetting of Footpath Slab and pointing in C.M (1:3) (Approved Rate)	Sqm	6357.46		
2	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 5.5 m3) (V-I.No 1.4,Page No-5 PWD SR 2021-22)	Cum	12902.39		
3	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates (V-1, P.No-15, I No-2.1.3 of PWD SR 2021-22)	Cum	1911.91		
4	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications.(V-III, I.No 13.1 Page No 99, PWD SR 2021-22) issue rate dated 07-04-22	Tn	138.66		

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

5	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates (V-1,P.No 17, I.No.2.4.2 of PWD SR 2021-22)	Cum	2227.93		
6	Providing and fixing precast reinforced cement concrete covering slabs of 10Cm thick made of M20 with OPC cement,with 20mm and down size graded granite metal coarse aggregate @0.70 mixed, Inculding providing and removing centering, shuttering, strutting propping etc., for edges of slabs with TMT steel (Fe500) cost of all materials, labour, all lead and lift, HOM of machinery, curing, including cost of reinforcement etc , complete as directed by the Engineer in charge of the work	Sqm	7431.83		
7	Providing and fixing RCC precast cover slab of 230mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	414.30		
8	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. Mix 1:3.6 (M10) Using 20 mm nominal size graded crushed coarse aggregates (V-I, No-2.1.4, P.No-15 of PWD SR 2021-22).	Cum	230.72		
9	Providing and fixing pre cast solid cement concrete kerb stones made out of M20 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete ,complete as directed by the Engineer in Charge of the work (Approved Rate)	Nos	17472.00		
10	Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces (V-III, P.No.56, I.No.8.10 of PW, PWD SR 2021-22)	Sqm	4037.60		

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

11	Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work ((V-I, P.No-8, I No-1.12 of PWD SR 2021-22)	Cum	8088.12		
12	Construction of Granular Sub-Base of required grading as per design mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401 .(V-III, I No-4.1V,P No-19,KPWD SR 2021-22)	Cum	4243.82		
13	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density (V-III, P.No-24,I No-4.27A)of PWD SR 2021-22).	Cum	5609.00		
14	Providing and applying primer coat with SS1 grade Bitumen Emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.90 kg per m2 using mechanical means. (V-III, P.No-29,I No-5.1(i) of PWD SR 2021-22).	Sqm	31872.27		
15	Providing and applying tack coat with RS1 Bituminous Emulsion using emulsion pressure distributor at the rate of 0.20 kg/m2 on the prepared bituminous surface cleaned with mechanical broom.(V-III, P.No-29,I No-5.3(i) of PWD SR 2021-22).	Sqm	76766.61		
16	Providing and laying Dense Graded Bituminous Macadam with 40/60 TPH capacity HMP using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 505 complete in all respects. (V-III, P.No-33,I No-5.12C of PWD SR 2021-22).	Cum	2041.07		

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

17	Providing and laying Bituminous Concrete with 40/60 TPH capacity hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 5.4 per cent of mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects (V-III, P.No.36, I.No.5 16C of PWD SR 2021-22).	Cum	2501.23		
18	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 g/ m2 area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35:2015.The finished surface to be level, uniform and free from streaks and holes.	Sqm	2411.70		
19	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 m3 in volume and stock piling at designated locations and disposal of dismantled materials and stacking serviceable and unserviceable materials separatel	Cum	398.48		
20	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:5:10 Using 40 mm nominal size graded crushed coarse aggregates	Cum	477.78		
21	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, , primer, sealant , curing of concrete slabs for 14- days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete as per the directions of the Engineer-in-charge of the work.(V-III, P.No-138,I No-20.29, KPWD SR 2021-22).	Cum	477.78		

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

22	Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per m2 over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level , including cost of materials, labour and Usage charges of machinery complete as per specifications.	Sqm	5044.85		
23	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km (V-III Page No.3, Item No.1.4 A of PWD SR 2021-22)	T.km	27704.65		
24	Earth work excavation for Foundation by mechanical means for all works & depth upto 3 m, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenaces required to complete the work Depth exceeding 1.5 m, but not exceeding 3 (V-I Page No.8, Item No.1.15.2 of PWD SR 2021-22)	Cum	350.33		
25	Providing and laying in position Reinforced cement concrete for all Foundation works. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticizers laid in finished layers, well compacted using needle vibrators, including all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates (V-I Page No.15, Item No.2.2.2.1 of PWD SR 2021-22)	Cum	83.21		
26	Providing and laying in position Reinforced cement concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/ trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement, dowel bars & formwork to be paid separately)M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates (V-I Page No.17, Item No.2.5.1 of PWD SR 2021-22)	Cum	70.46		

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

27	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6(1 cement: 6 coarse sand) (V-II Page No.9, Item No.5.4 of PWD SR 2021-22)	Cum	123.31		
28	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations and other similar works etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m. (V-I Page No.7, Item No.1.9 of PWD SR 2021-22)	Cum	480.90		
29	Providing Thermo-Mechanically Treated bars of grade Fe-500D or more Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position, binding and anchoring to adjacent members whereever necessary complete as per Design including cost of material, labour, usage charges complete as per specifications. (The laps and wastages shall not be measured separately) (V-II Page No.11.32, Item No.84 of PWD SR 2021-22)	Kgs	16974.33		
30	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x200x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications. (V-II Page No.17, Item No.6.32 of PWD SR 2021-22)	Sqm	557.07		
31	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x100x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.(V-II Page No.17, Item No.6.34 of PWD SR 2021-22)	Sqm	24.45		
32	Providing and laying water proofing treatment to the Roof with PU based single component elastomeric pure polyurethane based coating on New terrace/Chajjas/Sunken portion of WC:Bathroom, cold applied PU waterproofing membrane that is highly elastic with elongation greater than 400% and tensile strength greater than 2MPa as per ASTM D412. The waterproofing membrane to be applied in 2coats @ 1.6kg per m2 to achieve final DFT (dry film thickness) of 1mm including prime coat of epoxy primer @150 g per m2 and protection with 120gsm Geo-textile over the waterproofing membrane. The finished cost to include surface preparation, making coving at Junction, Bore Packing, treatment of construction joints completely as per specification & with a 10 years warranty on product & work from certified manufacturers as per the direction of the Engineer In charge.(V-II Page No.133, Item No.15.1 of PWD SR 2021-22)	Sqm	283.85		
33	Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, usage charges complete as per	Sqm	4.86		

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

	specifications (V-II Page No.99, Item No.12.11 of PWD SR 2021-22)				
34	Fixing of door frame in an existing opening including embedding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debris with lead upto 50 m. including cost of materials, labour charges, complete as per specifications (V-II Page No.105, Item No.12.51 of PWD SR 2021-22).	Nos	7.00		
35	Providing and fixing flush door shutter made out of solid core block board type, well seasoned , chemicaly treated hard wood battens and internal frame with minimum 45 mm wide wooden frame alround door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door useing liquid phenol formaldehyde resin as per IS specifications 2202 (part-I) 1991. from manufacturer complete as per spcification. 30 mm thick both side commercial (V-II Page No.105, Item No.12.51 of PWD SR 2021-22).	Sqm	98.28		
36	Providing & fixing of 2-track x 2-panel sliding windows made out of multi chambered UPVC(Matching to RAL-9016) sections and with minimum TiO2(Titanium Dioxide) at 6 PHR with TPE (Thermo Plastic Elastomer) and lead free, gaskets -grey color having isolated drainage and reinforced with Galvanized Iron profile through-out the window frame. The outer frame having an overall size of 44mm width x 40mmheight with reinforcement of 1mm thickness and Sash with overall size of 27mm X 53mm with UPVC honeycomb structure inside in lieu of GI reinforcement. Coextruded Glazing bead for fixing of glass shall be of size 9.5mm x 21.5mm. Windows shall be provided with 5mm plain float glass, standard hardware& single point locking system with Crescent Locks. Wall thickness of frame & sash shall be of 2 mm.Maximum possible size – 1219mm x 1219mm. (The cost is inclusive of all fixtures and separate charges for minor T&P's shall not be made) (V-II, Page No.110, Item No.12.84 of PWD SR 2021-22)	Sqm	25.20		
37	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to steel windows by welding (V-II, Page No.85, Item No.11.34A of PWD SR 2021-22)	Sqm	529.20		
38	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6 mm angle iron and 3 mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. Using M.S. angels 40x40x6 mm for diagonal braces including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.(V-II, Page No.75, Item No.11.5.1 of PWD SR 2021-22)	Sqm	9.45		

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

39	Providing 15 mm cement plaster on the rough side of single or half brick wall of mix 1:4 (1 cement: 4 fine sand) including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.(V-II, Page No.41, Item No.8.2.1 of PWD SR 2021-22)	Sqm	771.70		
40	Providing 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonary including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.(V-II, Page No.41, Item No.8.3.1 of PWD SR 2021-22)	Sqm	765.22		
41	Providing and laying flooring and steps fine machine polished granite stone slabs 20 mm thick on cement mortar bed 1:6, 20 mm thick, and joints finished with cement mortar 1:3 over existing cement concrete bed including cost of materials, mortar, labour, curing complete as per specifications.(V-II, Page No.64, Item No.9.30 of PWD SR 2021-22)	Sqm	228.09		
42	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ m2 including pointing the joints with white cement and matching pigments etc., complete (V-II, Page No.60, Item No.9.11 of PWD SR 2021-22)	Sqm	38.27		
43	Providing skirting, dadooing, rises of steps with white glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over existing rough plaster surface using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications.(V-II, Page No.65, Item No.9.38 of PWD SR 2021-22)	Sqm	61.65		
44	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade :Two coats on new work after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (V-II, Page No.48, Item No.8.39 of PWD SR 2021-22)	Sqm	755.06		
45	Providing White washing with lime to give an even shade :New work (three coats) with lime of approved quality, including cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (V-II, Page No.44, Item No.8.21 of PWD SR 2021-22)	Sqm	765.22		

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

46	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two coat applied @ 1.67 ltr/10 m² over and including priming coat of exterior primer applied @ 2.20 kg/10 m²) with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.(V-II, Page No.46, Item No.8.30 of PWD SR 2021-22)	Sqm	765.22			
47	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :Two coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.(V-II, Page No.48, Item No.8.41 of PWD SR 2021-22)	Sqm	25.20			
48	Providing and fixing chromium plated brass handles of 100/125 mm with necessary screws etc. Complete(V-II Page No.107, Item No.12.62 of PWD SR 2021-22)	Nos	14.00			
49	Providing and fixing ISI marked M.S. pressed butt hinges bright finished with necessary screws etc.125x65x2.12mm(V-II Page No.107, Item No.12.68.1 of PWD SR 2021-22)	Nos	24.00			
50	Providing and fixing bright finished brass tower bolts (barrel type) with necessary screws etc. Complete 250x10mm (V-II Page No.109, Item No.12.76 of PWD SR 2021-22)	Nos	8.00			
51	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid (V-II Page No.123, Item No.14.3.1 of PWD SR 2021-22)	Nos	6.00			
52	Providing and fixing white vitreous china laboratory sink with C.I. brackets, C.P. brass chain with rubber plug, 40 mm C.P brass waste and 40mm C.P. brass trap with necessary C.P. brass unions complete, including painting of fittings and brackets, cutting and making good the wall wherever required : Size 600x450x200 mm (V-II Page No.126, Item No.14.11.2 of PWD SR 2021-22)	Nos	4.00			

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

53	Providing and fixing white vitreous china flat back half stall urinal of size 580x380x350 mm with white PVC automatic flushing cistern, with fittings, standard size C.P. brass flush pipe, spreaders with unions and clamps (all in C.P. brass) with waste fitting as per IS : 2556, C.I. trap with outlet grating and other couplings in C.P. brass, including painting of fittings and cutting and making good the walls and floors wherever required : Single half stall urinal with 5 litre P.V.C. automatic flushing cistern (V-II Page No.124, Item No.14.5.1 of PWD SR 2021-22)	Nos	2.00		
54	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in charge. Concealed work, including cutting chases and making good the walls etc. 20mm nominal dia pipes (V-II Page No.124, Item No.13.32.2 of PWD SR 2021-22)	m	45.00		
55	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in charge. Concealed work, including cutting chases and making good the walls etc. 25mm nominal dia pipes (V-II Page No.124, Item No.13.32.3 of PWD SR 2021-22)	m	60.00		
56	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in charge. Concealed work, including cutting chases and making good the walls etc. 32mm nominal dia pipes (V-II Page No.124, Item No.13.32.4 of PWD SR 2021-22)	m	30.00		
57	Supplying PVC ringtite pipes conforming to IS 4985:2000 with latest amendments and conveying to worksite, rolling and lowering into trenches, laying true to line and level and perfect linking at joints, testing and commissioning, including loading unloading at both destinations and cuts of pipes wherever necessary including jointing of PVC pipes and specials (excluding cost of specials) with jointing of approved type, with all labour with all lead & lift including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation etc. complete and giving necessary hydraulic test to the required pressure as per ISS (Contractor will make his own arrangements for procuring water for testing) etc. for:PVC pipes 110mm dia., 6 kg/sqcm & class 3(Page No.134, Item No.1.7 of BWSSB SR 2021-22)	M	45.00		

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

58	quality (screwed end)(V-II Page No.115, Item No.13.6.1.2 of PWD SR 2021-22)	Nos			
59	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete(V-II Page No.115, Item No.13.5.2 of PWD SR 2021-22)	Each	4.00		
60	Providing and fixing PTMT pillar cock of approved quality and colour15 mm nominal bore, 125 mm long foam flow, weighing not less than 120 gms(V-II Page No.118, Item No.13.20.2 of PWD SR 2021-22)	Each	6.00		
61	Bottle trap 38 mm single piece moulded with height of 270 mm, effective length of tail pipe 260 mm from the centre of the waste coupling, 77 mm breadth with 25 mm minimum water seal, weighing not less than 263 gms (V-II Page No.129, Item No.14.37.2 of PWD SR 2021-22)	Each	6.00		
62	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 19/20mm dia 2mm thick conforming to IS 2509 with suitable size bends, metal/PVC junction boxes adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipes ends should be covred using PVC end enclosures. run with 18SWG.GI fish wire wherever necessary.19/20mm dia 2mm thick (Page No.1, Item No.1.2.1 of PWD Electrical SR2022-23)	m	100.00		
63	Providing and fixing Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including cost of materials, labour, usage charges ofmachinery complete as per specifications and as per directions of the Engineer-in-Charge. (V-2 Page No.82, Item No.11.25.2 of PWD SR 2021-22) Issue Rate On 07-04-22	Kg	462.00		
64	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 25mm dia 2mm thick conforming to IS 2509 with suitable size bends, metal/PVC junction boxes adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipes ends should be covred using PVC end enclosures. run with 18SWG GI fish wire wherever necessary.a)25mm dia 2 mm thick (Page No.1, Item No.1.2.2 of PWD Electrical SR 2021-22	m	100.00		
65	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 19/20mm dia 2mm metal/PVC junction boxes adhesive paste etc. By groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary.19/20mm dia 2mm thick(Page No.1, Item No.1.3.1 of PWD Electrical SR 2021-22)	m	100.00		

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

66	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 25mm dia 2 mm metal/PVC junction boxes adhesive paste etc. By groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary.a)25mm dia 2 mm thick (Page No.1, Item No.1.3.2 of PWD Electrical SR 2021-22)	m	100.00		
67	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 32mm dia 2.5mm metal/PVC junction boxes adhesive paste etc. By groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary.32mm dia 2.5 mm thick (Page No.1, Item No.1.3.3 of PWD Electrical SR 2021-22)	m	10.00		
68	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multistrand Copper conductor single core cable in open or concealed system of wiring with specified IS-694:1990 & conforming to GTP of Group-A (Page No.3, Item No.2.3 of PWD Electrical SR 2021-22). 1.0 Sqm	m	200.00		
69	1.5 Sqm	m	90.00		
70	2.5 Sqm	m	170.00		
71	4.0 Sqm	m	90.00		
72	10.0 Sqm	m	40.00		
73	Point wiring using Copper wire without switch Supplying and wiring adopting loop system in existing PVC Conduit/casing capping using 1100V Grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2x1.5 Sq.mm Cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose lenght in a wood/PVC round block. complete for each outlet.(5/2.3) Using class A materials (Page No.3, Item No.2.2 of PWD Electrical SR 2021-22). Short point up to 3mtrs from tapping point to out let via switch (Page No.3, Item No.2.2.1 of PWD Electrical SR 2021-22)	Point	36.00		
74	Medium point a above 3mtr up to 6mtr from tapping point to out let via switch (Page No.3, Item No.2.2.2 of PWD Electrical SR 2021-22)	Point	36.00		
75	Long point a above 6mtr up to 10mtr from tapping point to out let via switch (Page No.3, Item No.2.2.3 of PWD Electrical SR 2021-22)	Point	24.00		
76	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve , indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required conforming to IEC60898.5-32Amps DP (Page No.13, Item No.5.17 of PWD Electrical SR 2021-22). 6-32Amps SP	Each	15.00		
77	6-32 Amps DP	Each	15.00		
78	40 Amps TPN	Each	8.00		
79	50-63 Amps SP	Each	8.00		

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

80	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc , with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure,III-Single Door,Group A12Way SP &N (Page No.13, Item No.5.18.4 of PWD Electrical SR 2021-22)	Each	10.00		
81	Supplying and fixing regular MCB distribution boards on wall/wood board/flush mounting using required clamps, bolts, nuts etc. with provision for fixing suitable type capacity MCB's single phase/3 phase/single door with power coated painting etc., complete: Double door: 6 way TP &N , Group (A) (Page No.13, Item No.5.18.12 of PWD Electrical SR 2021-22)	Each	5.00		
82	Supplying and fixing 32Amps security and energy saving DP switch with key tag suitable to operate on 230 Volts, 50Hz AC supply & completely wired on existing box. (Page No.6, Item No.3.7 of PWD Electrical SR 2021-22)	Each	5.00		
83	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall 1-3 Way (Page No.5, Item No.3.4.1 of PWD Electrical SR 2021-22)	Each	25.00		
84	Supplying and fixing of 20/40 Watts heavy duty open construction Ferromagnetic copper ballast for fluorescent tubes : Supplying and fixing of 20/40 Watts heavy duty open construction Ferromagnetic copper ballast for fluorescent tubes, Class H Insulated copper wire, Vacuum impregnated high quality with Low loss silicon steel lamination operated on 240V,50Hz supply with IEC 60920 (Safety) & IEC 60921(Performance). Operating voltage range from 180V to 265V, 50Hz AC power Supply. (Page No.41, Item No.12.23 of PWD Electrical SR 2021-22)	Each	20.00		
85	Supply and fixing metal fan box with round hook (Page No.2, Item No.1.12 of PWD Electrical SR 2021-22)	Nos	12.00		
86	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293.(Page No.5, Item No.3.6 of PWD Electrical SR 2021-22) 6Amps SP Switch	Each	50.00		
87	6Amps 3way 5 pin socket	Each	20.00		
88	16Amps SP Switch	Each	10.00		
89	32Amps Flush/projected types DP switch	Each	10.00		
90	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall (Page No.5, Item No.3.4 of PWD Electrical SR 2021-22) 1-3Way	Each	20.00		
91	4-5Way	Each	20.00		
92	6Way	Each	20.00		
93	8Way	Each	24.00		
94	10-12Way	Each	16.00		

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

95	16Way	Each	4.00		
96	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. (Page No.5, Item No.3.5 of PWD Electrical SR 2021-22). 1 to 3 Module	Each	20.00		
97	4Moudule	Each	20.00		
98	6Moudule	Each	20.00		
99	8Moudule	Each	24.00		
100	10Moudule	Each	16.00		
101	12Moudule	Each	4.00		
102	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies for operation on 230 Volts, 50 Cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system.(84/9.3)56" Sweep (1400mm) Regular model (Page No.22, Item No.6.3.2 of PWD Electrical SR 2021-22)	Each	10.00		
103	Supplying and fixing of Electronic Ballast suitable for T8 Lamp with housing made of Pre-coated steel/PC, Operating voltage range from 180V to 265V, 50Hz AC power Supply flicker free warm start with over voltage protection, Inrush current protection, De-activated lamp protection & End of Lamp life protection with PF> 0.95 & TC(deg C) > 65 degC. Operating voltage range from 180V to 265V, 50Hz AC power Supply.(Page No.40, Item No.12.22.3 of PWD Electrical SR 2021-22)	Each	10.00		
104	Fixing all types and all capacities of fluorescent / false ceiling / spot light / CFL / LED fittings indoor on the wall / ceiling / rafters / girders using 23/0.0076" twin twisted PVC insulated wires, required Nos of round blocks and clamps. 14.7.1 On wall / ceiling / Rafter / Girders (Page No.45, Item No.13.7.1 of PWD Electrical SR 2021-22)	Each	30.00		
105	Geophysical investigation at site for sinking borewells for supplying drinking water to the habitation either through the Hand Pump MWS or P.W.S.S, by vertical electrical sounding by adopting Venner orSchlumbergers's method, including reconnaissance survey of geological formation. Geophysical investigation of existing ground water in the vicinity, its quality, quantity and acceptability of the users, indicating the location of the site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 metre in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instruments and accessories to work site, engaging technical personal and labour required etc. NOTE: 1) Additional rate on item 1&2 is allowed for drilling in over burden and fixing Casing pipes beyond 20 M (for fixing Casing pipes only) a) Above 20 M and upto 30 M - 15%, b) Above 30 M - 30% (Measurement of overburden is restricted to the depth of casing pipe fixed excluding initial depth of 20M and projection above ground level). 2) A sum of Rs. 100/- is to be deducted for Dry Borewell	Nos	1.00		

	towards yield test. (P.151, I.No-4 Code No-O040A) BWSSB SR 2021-22				
106	Sinking of Borewell of 165mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burdern upto 20 m. Fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicle, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (Excluding cost of casing pipes, collars, cap etc., complete)(P.151, I.No-1) BWSSB SR 2021-22. 0 to 50 m (Code No-O010A)	m	50.00		
107	50 to 100 m (Code No-O010B)	m	50.00		
108	100 to 150 m (Code No-O010C)	m	50.00		
109	150 to 200 m (Code No-O010D)	m	50.00		
110	200 to 250 m (Code No-O010E)	m	50.00		
111	250 to 300 m (Code No-O010F)	m	50.00		
112	300 to 350 m (Code No-O010G)	m	50.00		
113	Supply of ISI mark 175mm nominal bore,plain and steel casing pipe grade of steel Fe 410 of wall thickness conforming to IS 4270-2001 and latest ammendments, electrical resistance welded steel tubes, material and conforming to IS 1387-1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5-7m both ends threaded conforming to IS 554-1985 one end fixed with socket conforming to IS 4270-2001 and the other end with screwed pipes all shall be responsibaly free from defects. The tubes shall be responsible straight end should be with ISI marking weighing 25.10kg/m prices include Collar-Medium duty (P.154, I.No 32, O160A) BWSSB SR 2021-22	Rmtr	60.00		
114	Supply and delivery of galvanized mild steel tubes of 6mtr standard length heavy duty (C Class) as per IS 1239 (Part-I) 1990 with latest amendments with ISI Mark (one end fitted with Heavy Duty collar and other end fitted with protective cover) 50 mm (P. No.162, I. No. 33.1 BWSSB SR 2021-22)	Each	24.00		
115	PVC pipe - OD 250mm and 6 Kg/sqcm	Rmtr	6.00		
116	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper withflexible copper with low resistance conductor confirming to13:8130-1984 and virgin grade PVC insulation and powdercoating extruded PVC sheathed suitable for working voltageupto 1100 V as per IS-694:2010. 3C x 6 mm2 P. No. 4/ I No. 2.6.4 KPWD Electrical SR 2021-22	Mtr	620.00		
117	Providing,supplying to work site, Submersible Pump Set of 150mm dia suitable for bore well and confirming to IS 8034-2000;3Phase, SS Bowl & Impeller with Low volt Motor as per specifications,as per necessary ammendments and instructions of engineer incharge of work. 15.00 HP - 120 LPM @ 266 m = 23 STG Outlet Dia - 2.00"(P. No.161, I. No. 18.6, BWSSB SR 2021-22)	Nos	1.00		

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

118	Earthing: Supplying and fixing and wiring earth electrode for grounding circuits IC cutouts and other equipments on the meter board in the pit. The pits should be filled up with equal proportion of salt and charcoal 150mm around the pipe to complete depth. The connection from the pipe to the conduits etc. is to established through GI wire of sizes as per clause 7.3.3 of IS 732 using 12mm bolts, nuts, washers and check nuts, the pipe shall have 16 through holes of 12mm dia. (P. No.164, I. No. 45, BWSSB SR 2021-22)	job	1.00			
119	Supply and fixing polished wood board made of not lessthan 15mm thick plank on both sides of not more than 2pieces and fixing the same to the wall using tapered Invertedwooden plugs screws. 20" x 20" x 2.5" (P No. 10 No.5.6.6,Part-I Electrical SR 2021-22)	Each	1.00			
120	Supplying & fixing of Porcelain fuse channel with cut out onexisting wooden/panel using necessary nuts, bolts andwashers. 63 A (P No. 10 No.5.6.6,Part-I Electrical SR 2021-22)	Each	1.00			
121	Supplying & fixing miniature circuit breakers on existingMCB distribution boards using necessary fixing materialsand 'C' Type curve, indicator ON/OFF, energy cross-3 withShort circuit breaking capacity of 10K and complete wiring asrequired confirming to IEC 60898. 50-63 A TPN (P No. 13 I.No.5.17.9,Part-I Electrical SR 2021-22)	Each	1.00			
122	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum.(V-I.No 1.4,Page No-5 PWD SR 2021-22)	Cum	180.00			
123	Supplying and filling in plinth with sand under floors, foundation of Bridges including watering, ramming, consolidating and dressing complete.	Cum	36.00			
124	Supplying PVC ring type pipes conforming to IS 4985:2000 with latest amendments and conveying to worksite, rolling and lowering into trenches, laying true to line and level and perfect linking at joints, testing and commissioning, including loading unloading at both destinations and cuts of pipes wherever necessary including jointing of PVC pipes and specials (excluding cost of specials) with jointing of approved type, with all labour with all lead & lift including encasing the pipe around to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation etc. complete and giving necessary hydraulic test to the required pressure as per ISS (Contractor will make his own arrangements for procuring water for testing) etc.63mm outer dia, 6kg/sqcm & class 3 for:	Mtr	400.00			

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

125	Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. Including cost of all labour complete as per specifications P. No. 7, I No. 1.10,V-I PWD SR 2021-22	Cum	120.00		
126	Supplying fully automatic star-delta starter unit push button type with suitable wires, 3 contactors, one adjustable thermal timer mounted on a common base plate held in steel enclosure for use on 400/440 V 3 phase and wired after fixing to the existing wooden board for motor. Above 12.5 HP upto 25 HP (P No. 10 I.No.5.2.2,Part-I Electrical SR 2021-22)	Nos	1.00		

SECTION 8: DRAWINGS
(Enclosed)

SECTION 9: BILL OF QUANTITIES

(1) Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of Quantities (refer: ITB Clause 11.2 and CC Clause 37.2).
(2) Unit rates and prices shall be quoted by the Tenderer in Indian Rupees.
(3) Where there is a discrepancy between the rate in figures and words, the lower of the two will govern. [ITT Cla
(4) Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity, the unit rate quoted shall govern [ITT Clause 24.1 (b)]
(5) GST will be paid separately to the Tendered Amount

SECTION 10: FORMAT OF BANK GUARANTEE FOR SECURITY DEPOSIT

To: ..... *[name of Employer]*
..... *[address of Employer]*

WHEREAS ..... *[name and address of Contractor]* (hereinafter called "the Contractor") has undertaken, in pursuance of Contract No. ..... dated : ..... to execute ..... *[name of Contract and brief description of Works]* (hereinafter called "the Contract");

AND WHEREAS it has been stipulated by you in the said Contract that the Contractor shall furnish you with a Bank Guarantee by a recognized bank for the sum specified therein as security for compliance with his obligations in accordance with the Contract;

AND WHEREAS we have agreed to give the Contractor such a Bank Guarantee;

NOW THEREFORE we hereby affirm that we are the Guarantor and responsible to you, on behalf of the Contractor, up to a total of Rs. ..... *[amount of guarantee]* [38] Rupees..... *[in words]*, and we undertake to pay you, upon your first written demand and without cavil or argument, any sum or sums within the limits of ..... *[amount of guarantee]*[39] as aforesaid without your needing to prove or to show grounds or reasons for your demand for the sum specified therein.

---

[38] An amount shall be inserted by the Guarantor, representing the percentage of the Contract Price specified in the Contract

[39] An amount shall be inserted by the Guarantor, representing the percentage of the Contract Price specified in the Contract

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

We hereby waive the necessity of your demanding the said debt from the Contractor before presenting us with the demand.

We further agree that no change or addition to or other modification of the terms of the Contract or of the Works to be performed there under or of any of the Contract documents which may be made between you and the Contractor shall in any way release us from any liability under this guarantee, and we hereby waive notice of any such change, addition or modification.

This guarantee shall be valid until 30 days from the date of expiry of the Defects Liability Period.

Signature and seal of the guarantor _____
Name of Bank _____
Address _____
Date _____

[ITT Cla

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV